



## **ADDENDUM #3**

**September 8, 2011**

RE: Harrisburg Area Community College  
Blocker Hall Chiller Replacement  
Solicitation #RFB11-23

From: Eastern PCM, LLC  
Construction Manager – HACC  
645 N. 12<sup>th</sup> Street, Suite 200  
Lemoyne, PA 17043

To: All Planholders

---

This Addendum is hereby made part of the Plans and Project Manual dated August 12, 2011 for the above referenced project. The provisions of this Addendum are intended to supplement the provisions of the Plans and Project Manual and/or supersede them where contradictory thereto.

This Addendum contains changes to the requirements of the Plans and Project Manual. Such changes shall be incorporated into the Plans and Project Manual and shall apply to work with the same meaning and force as if they had been included in the original Plans and Project Manual. Where this Addendum modifies a portion of a paragraph or phrase of the Project Manual, the remaining unmodified portion of the paragraph or phrase shall remain in force.

The conditions and terms of the Plans and Project Manual shall govern work described in this Addendum. Whenever the conditions of work, or the quality or quantity of materials or workmanship are not fully described in this Addendum, the conditions of work etc. included in the Plans and Project Manual for similar items of work shall apply to the work described in this Addendum. If no similar items of work are included in the Plans and Project Manual, the quality of material and workmanship shall be subject to the written acceptance of the Architect.

### **2.2 CHANGES TO THE PROJECT MANUAL**

A. Specification Section 15641 – Open-Circuit, Mechanical-Draft Cooling Towers

Paragraph 1.5 **ADD** the following:

“B. Provide all product data and chemical treatment requirements to Nalco Chemical”

B. Specification Section 15900 – HVAC Instrumentation and Controls

**REVISE** Paragraph 1.3 B to read:

“Disconnect existing point from JCI NU\_NCM control panels. Delete all point references in the existing NCM database. Furnish and install new JCI Metasys FEC control panel, to be located in the basement mechanical room. Install and wire all new Chilled Water and Condenser Water points to the new FEC control Panel. Extend the BacNet FC bus from the penthouse NAE controller to the new FEC. Program all new Chilled water and Condenser water point references into the existing NAE database.”

**END OF ADDENDUM**



Please sign and return this page, via fax, to Eastern PCM, LLC at (717) 233-1666 indicating receipt of this Addendum.

**HACC Blocker Chiller Replacement  
SOLICITATION #RFB11-23**

Addendum #\_\_\_\_\_ has been received.

**Company:** \_\_\_\_\_  
Print Company Name

**Received By:** \_\_\_\_\_  
Print Name Signature

**Date:** \_\_\_\_\_

**Please check one:**

- \_\_\_\_\_ We are bidding as a prime contractor  
\_\_\_\_\_ We are not bidding  
\_\_\_\_\_ We are a sub-contractor